

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
GREENE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Greene County, Mississippi at the Greene County Courthouse, Leakesville, Mississippi, until 10:00 am on the 26th day of March, 2018 and shortly thereafter publicly opened for the construction of 0.464 miles of BRIDGE REPLACEMENT on the SITE "A" VERNAL RIVER RD SITE "B" HIGH SCHOOL RD being known as Project No. SAP-21(81) in Greene County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA. 271+83)	1.000	UN
REMOVAL OF BRIDGE (STA. 536+15)	1.000	UN
REMOVAL OF PAVEMENT, ALL DEPTHS	2,357.000	SY
REMOVAL OF PIPE (ALL SIZES)	257.000	LF
UNCLASSIFIED EXCAVATION (FM)	587.000	CY
BORROW EXCAVATION (F.M.E.)	2,508.000	CY
(CONTRACTOR FURNISHED) (CLASS 5)		
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	436.000	CY
CRUSHED STONE (SIZE 610)	861.000	TON
HOT MIX ASPHALT, (ST) (9.5MM)	455.000	TON
HOT MIX ASPHALT, (ST) (12.5MM)	782.000	TON
CLASS B STRUCTURAL CONCRETE,	1.134	CY
MINOR STRUCTURES		
18" REINFORCED CONCRETE PIPE, CLASS III	184.000	LF
24" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF
36" REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
18" REINFORCED CONCRETE PIPE END SECTION	12.000	EA
24" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
36" REINFORCED CONCRETE PIPE, END SECTION	4.000	EA
GUARD RAIL, "W" BEAM, COMPLETE-IN-PLACE	300.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I", THRIE BEAM	8.000	EA
GUARD RAIL, TERMINAL END SECTION	8.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	14.000	EA

MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE COLD PLASTIC EDGE STRIPE (CONTINUOUS WHITE)	0.080	MI
4" WIDE COLD PLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)	0.080	MI
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.847	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	0.847	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	56.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	8.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	5.380	TON
COMMERCIAL FERTILIZER (13-13-13)	2.690	TON
AMMONIUM NITRATE	0.270	TON
SEEDING	2.690	AC
VEGETATIVE MATERIALS FOR MULCH	5.380	TON
SOLID SODDING	53.300	SY
EXCELSIOR BLANKET	800.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	5,630.000	LF
WATTLES, 20"	1,200.000	LF

BRIDGE SITE A ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	670.000	LF
18" PRE-FORMED PILE HOLES	607.000	LF
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	240.000	LF
31.17' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31.17' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.17' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	163.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	519.000	SY

BRIDGE SITE B ITEMS:

TEST PILE	2.000	EA
-----------	-------	----

CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	590.000	LF
18" PRE-FORMED PILE HOLES	450.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31.00' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31.00' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	188.000	TON
GEOTEXTILE UNDER RIPRAP TYPE V, AOS 0.21-0.43	650.000	SY

PROJECT NO. SAP-21(81)
GREENE COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Greene County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Donald E. Walker, County Engineer for Greene County, Mississippi, P. O. Box 16496, Hattiesburg. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable Certified check or bid bond for five percent (5%) of the total bid, made payable to Greene County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Jerry Mills, President
Greene County Board of Supervisors

Dates of Publication: February 22, 2018 & March 1, 2018